



The Village of Bald Head Island

Wastewater Collection System Maintenance Phase III

**Addendum
Posted 1/6/2025**

Project Contact: Mark Johnston, Project Manager

Email: mjohnston@villagebhi.org

Date(s) of Release: December 3, 2024, and reposted December 19th

- Can you supply the pump conditions, i.e., discharge head and flow, for each station?

This information is not available at this time. However, contractors can schedule a site visit prior to the bid closing to make observations.

- Is there a bypass connection for these stations or a manhole on the downstream side in close proximity?

No, the sewer systems at all 3 locations are forced mains.

- Can you supply a sketch or as-built drawings for the wet well replacements?

This information is not available at this time. However, contractors can schedule a site visit prior to the bid closing to make observations.

- Will the new check valves remain in the wet well or be relocated outside the wet well?

The new check valves should be relocated outside the wet well in their own vault.

1. What discharge pipe material/schedule is required for each station?

PVC Schedule 80

2. Do you have a spec for the wet well coating desired at Royal James?

No, the Village will require Industry standards applied by a Village approved repeatable contractor.

3. At Loggerhead, will BHI accept a new wet well inside the existing wet well like at Morning Wobbler?

If the bidder deviates from the bid specifications, please detail proposed change in proposal

**P.O. Box 3009 • BALD HEAD ISLAND, NC 28461
(910) 457-9700 • FAX (910) 457-6206 • WEBSITE: <http://www.villagebhi.org>**

Wastewater Collection System Maintenance Phase III

Addendum

Posted 1/6/2025

4. On the pump stations with new wet wells required (Morning Wobbler and Loggerhead) will the new wet well interior need to be coated?

No

5. Does BHI have a map of the sewer system showing gravity lines and force mains coming into or leaving each station including pipe size?

The Village mapping is limited and will be available to the awarded contractor.

6. Does this project require any bonds?

Payment and performance bonds in the amount of 100% of the contract sum pursuant to NC Gen Sta, 44a-26 will be required.

The following pictures were taken on 12.5.24
Royal James



Wastewater Collection System Maintenance Phase III
Addendum
Posted 1/6/2025



Mourning Warbler



SBHW

Wastewater Collection System Maintenance Phase III
Addendum
Posted 1/6/2025



Example Pictures of a rebuilt panel-Dune Ridge Main

Wastewater Collection System Maintenance Phase III
Addendum
Posted 1/6/2025



Wastewater Collection System Maintenance Phase III
Addendum
Posted 1/6/2025

