



The Village of Bald Head Island

Dowitcher Stormwater Pipe Install

Date: 4/8/26

The Village of Bald Head Island is seeking bids to install approximately 500' of 4" PVC stormwater pipe. Quotes should be returned to the contact information found below prior to 4/17/2026. Please contact the *Village Representative* (information below) to schedule a required walkthrough.

The bid should include all labor and materials.

The work will include, but not be limited to:

- Purchase, deliver and install approximately 500' of 4" PVC.
- Make two road cuts to install stormwater pipe.
- Attach pipe to existing standpipe at Stede Bonnett and run piping to existing castle box on Dowitcher.
- Make and repair knock out hole to install 4" pipe into the castle box.
- Repair the road cuts with ABC base course (Village will patch)
- Backfill and dress up the site after the pipe installation.

Vendor information and response

Company Name:

Address:

Contact person:

Total Cost Including labor and materials:

Start Date:

Final Completion Date:

Date and Signature:

Village Representative:

Mark Johnston
Public Services
mjohnston@villagebhi.org